

BELZONA REPAIR TO INTERNAL ROOF DRAIN STILL OK 24 YEARS LATER

ID: 1008



PROBLEM

Hit by a fork lift truck, the pipe broke off at the floor level and leaked water everytime it rained.

APPLICATION SITUATION

Internal downpipe, part of roof drainage system.

APPLICATION METHOD

Application carried out in accordance with a modified Belzona Know-How System Leaflet VPF-11b. Belzona® 4111 was packed around the break.

BELZONA FACTS

To change the broken pipe would involve a pipefitting/labor crew at least a week to excavate down below the floor three feet. Belzona application took just 20 minutes to complete. 8 man crew, 40 hours labor at \$50.00/hr = \$16,000 saved. Revisited February 2008, still performing.

INDUSTRY

Buildings & Structures

LOCATION

Auto manufacturer, Wentzville, MO

APPLICATION DATE

Summer 1984

PRODUCTS

Belzona 4111 (Magma Quartz)

SUBSTRATE

Steel and concrete

PHOTOS

1. Broken pipe, summer 1984
2. Repair completed
3. Revisited February 2008 and still performing

For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured
under an ISO 9001 Registered
Quality Management System.

www.belzona.com

