

CONCRETE PUMP PLINTHS REPAIRED WITH BELZONA

ID: 10251



PROBLEM

Customer was facing issues with damaged concrete pump plinths at a pumping station which had previously been repaired with cement/concrete material, which had failed after a period of time due to vibrations from the pumps. The customer was looking for a more permanent long term solution for the application.

APPLICATION SITUATION

After carrying out a site survey, Belzona 7111 Chocking compound was recommended for the repair of the five plinths. All loose concrete was removed back to solid concrete. Shuttering was cut to size, coated with a release agent and assembled around the plinths. Belzona 7111 was mixed and poured into the dammed voids and allowed to cure. Once cured, shuttering was removed.

APPLICATION METHOD

Rebuilding of the plinths was performed in accordance with leaflet (FPA-01). Manual hand tools were used to remove loose debris and the shuttering was treated with a release agent. Belzona 7111 was poured into the shuttering.

BELZONA FACTS

Belzona 7111 is a long term, durable chocking compound that is a viable replacement for concrete plinths to withstand physical and thermal shocks.

INDUSTRY

Water / Wastewater

LOCATION

Newcastle

APPLICATION DATE

March 2026

PRODUCTS

Belzona 7111

SUBSTRATE

Concrete

PHOTOS

1. Concrete plinths had been worn away due to vibration from pumps
2. The plinths required a long term durable solution that can withstand the effects of constant vibration
3. The shuttering is applied around concrete plinths and Belzona 7111 is poured into the recess
4. Belzona 7111 is cured and the plinths now have a durable base for the pumps

For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured under an ISO 9001 Registered Quality Management System.

www.belzona.com

