

BELZONA SEALS UPPER FLOOR PUMP ROOM

ID: 1145



PROBLEM

Copper pipes leaking water on the floor was leaking through the concrete to the lower level.

APPLICATION SITUATION

Pump room at hospital positioned on floor above computer room.

APPLICATION METHOD

Application was carried out using a modified Belzona Know-How System TCC-15.

After washing and removing dirt from floor Belzona® 5811 was used to coat the entire floor plus 6 inches up the wall to completely encapsulate the area and to form a containment area.

BELZONA FACTS

This application saved the hospital tens of thousands of dollars due to the last time the floor leaked it ruined all of the PCs below.

INDUSTRY

Buildings & Structures

LOCATION

County Hospital, Colton California U.S.A.

APPLICATION DATE

2007

PRODUCTS

Belzona 5811 (Immersion Grade)

SUBSTRATE

Concrete

PHOTOS

1. The pump room showing the pipes that keep leaking
2. Reinforcement tape used for edges
3. Back of pump room
4. Finished floor

For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured under an ISO 9001 Registered Quality Management System.

www.belzona.com

