

BELZONA REPAIRS AN UNDERGROUND SEWAGE PLANT

ID: 1905



PROBLEM

Prior to the application of a Belzona coating, it is required that new concrete should be allowed to cure for 28 days or until the moisture content has dropped below 6%. Unfortunately, in this application the customer could not wait for so long.

APPLICATION SITUATION

Plinths were built out of concrete as a support for the tanks.

APPLICATION METHOD

Coating of steel pannels with Belzona 5811 and bonding of these pannels in place onto the fresh concrete. Then, after the tank would be in place and the concrete had sufficiently cured, the panel edges and seams would be stripe coated, fully encapsulating the concrete.

BELZONA FACTS

All panels were successfully coated and assembled in place on time, saving the customer money and time.

INDUSTRY

Water / Wastewater

LOCATION

Underground sewage plant / UK

APPLICATION DATE

2011

PRODUCTS

Belzona 5811 (Immersion Grade)

SUBSTRATE

Concrete

PHOTOS

1. Tank construction
2. Before the application
3. Application of Belzona 5811
4. Completed application

For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured under an ISO 9001 Registered Quality Management System.

www.belzona.com

