

BELZONA REPAIRS MORE THAN 300 SPALLED CONCRETE LOCATIONS

ID: 6347



PROBLEM

Chunks of concrete were falling from various cracked and spalled areas of the building façade, causing concern for the public below.

APPLICATION SITUATION

Large office building with associated car park.

APPLICATION METHOD

The application was undertaken in accordance with Belzona System Leaflet WPA-4. In order to access exterior areas high up on the building, a Spider MEWP (Mobile Elevating Work Platform) was used. As the building's façade is made of red brick, a powder tint was added to the Belzona 4141, ensuring the system blended in with the surrounding substrate and provided an aesthetic finish. Temporary formers were used to support the Belzona material during application and to assist in reforming edge details.

BELZONA FACTS

The extensive repair work was completed in three months, (working weekends only), a small amount of time considering over 300 repair and protection applications were carried out.

INDUSTRY

Buildings & Structures

LOCATION

Office building, Manchester, UK

APPLICATION DATE

August 2015

PRODUCTS

Belzona 4141 (Magma-Build)

SUBSTRATE

Red Brick and concrete

PHOTOS

1. Deteriorated overhead lintel 2. Lintel rebuilt with colour matched Belzona 4141 3. Spalled overhead concrete 4. Overhead concrete repairs in progress

For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured under an ISO 9001 Registered Quality Management System.

www.belzona.com

