

BELZONA BONDS NEW BRACKETS TO TANK ROOF

ID: 7866



PROBLEM

The company needed a solution to bond the brackets of their new water sprinkling and foaming systems on several oil tanks. The problem here was that hot work and grit blasting (due to the dust created) were not allowed on site.

APPLICATION SITUATION

Water sprinkling and foaming systems on top of oil tanks.

APPLICATION METHOD

For each tank, the substrate was prepared with a dust free blasting system in order to achieve the right surface roughness without generating dust and potential fire hazards near the oil. Then, the brackets were bonded using Belzona 1111. Over 1000 brackets/support were bonded over 7-8 different storage tanks. 8 brackets were bonded on the side of a few tanks, the remaining brackets were bonded on the top of the tanks. The vertical brackets were help in place using magnets and vice mechanisms, while the brackets on the roof were bonded without additional weight or pressure during the curing process.

BELZONA FACTS

The combination of dust free blasting and cold bonding were the selling points for the client here, as the work was completed whilst the tanks were full of potentially explosive liquids. The entire project took around 13 weeks instead of 8 which were originally planned due to weather conditions, but the contractor was very satisfied with the overall work.

INDUSTRY

Chemical & Petrochemical

LOCATION

Petrochemical Plant, Netherlands

APPLICATION DATE

September 2018

PRODUCTS

Belzona 1111 (Super Metal)

SUBSTRATE

Steel

PHOTOS

- 1- Overview of the tank roof
- 2- Final application
- 3- Zoom on a cold bonded bracket

For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured
under an ISO 9001 Registered
Quality Management System.

www.belzona.com

