

BELZONA SOLUTION DIFFICULT RACKING ISSUE

ID: 9879



For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured
under an ISO 9001 Registered
Quality Management System.

www.belzona.com



Copyright © 1952-2026 Belzona International Limited.

PROBLEM

New racking was required due to expansion, but the area assigned was showing issues and the engineers were worried that the installation of the racking would not be approved by inspectors under the Provision and Use of Work Equipment Regulations 1998 (PUWER)
It was decided to ask the local Belzona engineer for a spec on a solution to install a stronger pad for the uneven target areas

APPLICATION SITUATION

The Belzona solution offered an extremely quick, durable and exceptionally strong solution to the issue of the uneven floor area. It would have been impossible to chock or shim the floor in a traditional way as the gaps were far too big to create a stable surface for the 3 shelf racking. Belzona offered the perfect solution

APPLICATION METHOD

The area was marked out and a frame was set to level. This frame was coated with Belzona 9411 release agent
The area was made rough, using cordless grinders with flap wheels and the area was vacuumed and cleaned
Belzona 4911 TX Conditioner was applied to the area as per the Belzona 4911 Instructions for Use
Following this, the Belzona 4111 resins were mixed in a receptacle. The Belzona 4111 aggregate was added and mixed well
This was applied inside the frame and compressed/levelled using a finishing trowel.
Any unfinished external areas were also repaired using the system as above to leave a solid, level pad for the bolting of the racking to take place

BELZONA FACTS

Time was of the essence for the engineers who were required to deliver the new racking area by a certain date. New stock was ordered and they had to be prepared and ready to receive it, As the installation of the racking needed to meet the regulations set out under PUWER, the Belzona solution was perfect for installation time and completed result. To have installed a new concrete area would have meant saw-cutting the floor, breaking out, casting a new part of the slab and awaiting setting of the concrete, which could have been up to 28 days. With the Belzona solution, the racking was fitted just 2 days after application

INDUSTRY

General Industry

LOCATION

Mansfield

APPLICATION DATE

PRODUCTS

Belzona 4111 (Magma-Quartz)
Belzona 4911 (Magma TX Conditioner)

SUBSTRATE

Concrete

PHOTOS

1. Floor failed where racking was due to be placed
2. Opening up into the area of repair
3. This shows the 500mm x 500mm pad constructed from Belzona 4111
4. A further view of the new pad

For more examples of Belzona Know-How in Action, please visit khia.belzona.com

Belzona products are manufactured
under an ISO 9001 Registered
Quality Management System.

www.belzona.com

